



## GUTTER TERMINATION

DRAWING: SOP-011

SCALE: Not to scale

EFFECTIVE DATE: 15-03-2019



# Gutter Termination

Prior to Membrane Installation, Review the Data Sheet

## Surface Prep

It is the contractor's responsibility to inspect all areas which are to receive the waterproofing membrane and report any unsatisfactory conditions to the main contractor. Refer to the technical data sheet for detailed specifications for preparing various substrates.

The surface to be waterproofed must be clean and sound. Remove all dust, dirt, laitance or any other contaminants which may hinder adhesion of the membrane.

## Special Notes

- (i) Flange min 100mm

Seal metal profile with Sopramastic Alu or a compatible sealant approved by Allnex.