



**FLOOR TO WALL JUNCTION WITH
REGLET TERMINATION
FULLY ADHERED DOUBLE LAYER
SYSTEM WITH A FILLET**

DRAWING: SOP-003

SCALE: Not to scale

EFFECTIVE DATE: 15-03-2019



Floor to Wall Junction With Reglet Termination

Fully Adhered Double Layer System With a Fillet

Prior to Membrane Installation, Review the Data Sheet

Surface Prep

It is the contractor's responsibility to inspect all areas which are to receive the waterproofing membrane and report any unsatisfactory conditions to the main contractor. Refer to the technical data sheet for detailed specifications for preparing various substrates.

The surface to be waterproofed must be clean and sound. Remove all dust, dirt, laitance or any other contaminants which may hinder adhesion of the membrane.

Special Notes

- (i) Elastocol 500 or Antirock Primer
- (ii) Field membrane stopped at transition, upturn flashed with separate piece of membrane.

Seal top edge of metal flashing with Sopramastic Alu or compatible sealant approved by Allnex.