



ROOF/PLAZA DECK CONSTRUCTION JOINT

DRAWING: SOP-017

SCALE: Not to scale

EFFECTIVE DATE: 15-03-2019



Roof/Plaza Deck Construction Joint

Prior to Membrane Installation, Review Data Sheet

Surface Prep

It is the contractor's responsibility to inspect all areas which are to receive the waterproofing membrane and report any unsatisfactory conditions to the main contractor. Refer to the technical data sheet for detailed specifications for preparing various substrates.

The surface to be waterproofed must be clean and sound. Remove all dust, dirt, laitance or any other contaminants which may hinder adhesion of the membrane.

Special Notes

- (i) Use the base sheet waterproofing membrane used on the system as reinforcing membrane.